

DIVISION 09 – SIGNING

09 10 00 GENERAL PROVISIONS

- A. All work in this Division shall be completed in accordance with the provisions of Division 9 of the North Carolina Department of Transportation Standard Specifications for Roads and Structures 2006 Edition (hereinafter referred to as *Standard Specifications*) except as amended or supplemented herein.

09 20 00 SPECIAL PROVISIONS-NCDOT

01. STREET SIGNS AND MARKERS AND ROUTE MARKERS:

(7-1-95)

SP9 R01

1. Move any existing street signs, markers, and route markers out of the construction limits of the project and install the street signs and markers and route markers so that they will be visible to the traveling public if there is sufficient right of way for these signs and markers outside of the construction limits.
2. Near the completion of the project and when so directed by the Engineer, move the signs and markers and install them in their proper location in regard to the finished pavement of the project.
3. Stockpile any signs or markers that cannot be relocated due to lack of right of way, or any signs and markers that will no longer be applicable after the construction of the project, at locations directed by the Engineer for removal by others.
4. The Contractor will be responsible to the owners for any damage to any street signs and markers or route markers during the above described operations.
5. No direct payment will be made for relocating, reinstalling, and/or stockpiling the street signs and markers and route markers as such work will be considered incidental to other work being paid for by the various items in the contract.

02. STEEL U-CHANNEL POSTS:

(7-18-06)

SP9 R02

Amend the *2006 Standard Specifications* as follows:

Page 9-15 Subarticle 903-3(D) first paragraph, last sentence, delete the last sentence and add the following:

Use posts of sufficient length to permit the appropriate sign mounting height. Spliced posts are not permitted on new construction.

09 30 00 SPECIAL PROVISIONS-ADDITIONAL